

Tributary debris fans and the late Holocene alluvial chronology of the Colorado River, eastern Grand Canyon, Arizona

Richard Hereford

Kathryn S. Thompson

Kelly J. Burke

} U.S. Geological Survey, 2255 N. Gemini Drive, Flagstaff, Arizona 86001

Helen C. Fairley } National Park Service, Grand Canyon National Park, P.O. Box 129,
Grand Canyon, Arizona 86023-0129

ABSTRACT

Bouldery debris fans and sandy alluvial terraces of the Colorado River developed contemporaneously during the late Holocene at the mouths of nine major tributaries in eastern Grand Canyon. The age of the debris fans and alluvial terraces contributes to understanding river hydraulics and to the history of human activity along the river, which has been concentrated on these surfaces for at least two to three millennia. Poorly sorted, coarse-grained debris-flow deposits of several ages are interbedded with, overlie, or are overlapped by three terrace-forming alluviums. The alluvial deposits are of three age groups: the striped alluvium, deposited from before 770 B.C. to about A.D. 300; the alluvium of Pueblo II age deposited from about A.D. 700 to 1200; and the alluvium of the upper mesquite terrace, deposited from about A.D. 1400 to 1880. Two elements define the geomorphology of a typical debris fan: the large, inactive surface of the fan and a smaller, entrenched, active debris-flow channel and fan that is about one-sixth the area of the inactive fan. The inactive fan is segmented into at least three surfaces with distinctive weathering characteristics. These surfaces are conformable with underlying debris-flow deposits that date from before 770 B.C. to around A.D. 660, A.D. 660 to before A.D. 1200, and from A.D. 1200 to slightly before 1890, respectively, based on late-19th-century photographs, radiocarbon and archaeological dating of the three stratigraphically related alluviums, and radiocarbon dating of fine-grained debris-flow deposits. These debris flows aggraded the fans in at least three stages beginning about 2.8 ka, if not earlier in the late Holocene. Several main-stem floods eroded the margin of the segmented fans,

reducing fan symmetry. The entrenched, active debris-flow channels contain deposits <100 yr old, which form debris fans at the mouth of the channel adjacent to the river. Early and middle Holocene debris-flow and alluvial deposits have not been recognized, as they were evidently not preserved adjacent to the river or are buried by younger deposits.

INTRODUCTION

Debris fans and related alluvial terraces are distinctive geomorphic features along the Colorado River in Grand Canyon (Hamblin and Rigby, 1968; Dolan et al., 1978). Fans develop at the mouths of tributary streams where large boulders of locally derived bedrock are deposited in the channel of the Colorado River by debris flows (Webb et al., 1989; Melis and Webb, 1993). The river is unable to move the large boulders except during relatively infrequent and large floods. As a result, the course of the river between bedrock walls, the presence and severity of rapids, and the location of Colorado River terraces are controlled by these coarse-grained deposits (Graf, 1979; Howard and Dolan, 1981; Kieffer, 1985; Webb et al., 1988; Schmidt and Graf, 1990).

Interest in debris fans and alluvial terraces of the Colorado River stems partly from the close association of fans and terraces with human activity in Grand Canyon. Archaeologic sites are abundant along the Colorado River in the study area (Fig. 1), averaging more than five per kilometer (Fairley et al., 1994). The sites are closely associated with terraces and debris fans that prehistoric people used for many purposes, including camp sites, agriculture, and construction of masonry structures (Hereford et al., 1993). Most sites are affiliated with the

Pueblo II Anasazi, dating between A.D. 1000 and 1150 (Euler and Taylor, 1966), although sites range in age from about 800 B.C. to the early 20th century (Jones, 1985; Altschul and Fairley, 1989). Modern man uses these same deposits for recreational purposes while hiking or rafting through Grand Canyon. The white-water rapids at the distal margin of many fans as well as the spectacular scenery of Grand Canyon attract 22 000 rafters annually who experience firsthand the powerful waves and swift currents (Stevens, 1990). In addition, most of the alluvial sand deposited by the Colorado River accumulates near the debris fans (Schmidt and Graf, 1990); these deposits form the substrate for riparian vegetation, which in turn supports the diverse riparian ecosystem of the Colorado River (Carothers and Brown, 1991, p. 111–167).

The study area borders the Colorado River in easternmost Grand Canyon, Arizona, downstream of the junction with the Little Colorado River (Fig. 1). The area lies entirely within the “Furnace Flats” fluvial geomorphic reach defined by Schmidt and Graf (1990, Table 1), extending from river mile 61.6 to 77.4, which is 61.6 to 77.4 miles downstream of the Compact Point near Lees Ferry, Arizona. This reach is part of the Chuar Segment of Grand Canyon, as defined by Potochnik and Reynolds (1990) on the basis of distinctive tributary canyons with broad open valleys. Elevation at the river is about 800 m and elevation at Desert View on the South Rim is 2282 m. The Furnace Flats reach is characterized by a relatively wide, shallow channel with slope of 0.0021. Bedrock at river level is mainly the Dox Formation of Huntton et al. (1986) with minor outcrops of the Cardenas Lavas of Hendricks and Stevenson (1990), which are both Middle Proterozoic. The Dox is rel-




Figure 1. Study area in eastern Grand Canyon. Pattern shows segmented fans; boxes show areas mapped on large-scale topographic maps (Hereford et al., 1993).

actively nonresistant and easily eroded; as a result Grand Canyon is unusually wide in the study area, although channel width and slope are similar to several other geomorphic reaches.

Debris fans of eastern Grand Canyon are segmented into surfaces of different ages; segmentation as used in this report is discussed by Cooke et al. (1993, p. 179–184). The debris fans are evidently similar to Type IB alluvial fans of Blair and McPherson (1994, p. 394–395), except that fan margins are extensively eroded by the Colorado

River. This type of fan, like those of eastern Grand Canyon, has a stratigraphic record dominated by clast-rich debris flows with minor interbedded fluvial gravels.

Previous Studies

Previous geomorphic studies have concentrated on the relation of alluvial deposits of the Colorado River to debris fans, the hydraulics of the rapids and flood-related geomorphic evolution of debris fans, and the processes and frequency of debris-flow

sediment transport. These studies dealt primarily with active debris fans and alluvial deposits that are younger than the debris fans and terraces discussed in this report. A flood history of the Colorado River was developed by O'Connor et al. (1994), who found that at least 15 floods with peak discharge $>5500 \text{ m}^3/\text{s}$ occurred in the past 4500 yr. For comparison, before closure of Glen Canyon Dam in 1963, the largest flood of the gaged record near Lees Ferry was $6200 \text{ m}^3/\text{s}$ and the mean annual flood was $2200 \text{ m}^3/\text{s}$. Regulated streamflow reduced the mean annual flood to $800 \text{ m}^3/\text{s}$ (Williams and Wolman, 1984, p. 10–11) and the largest flood since 1963 has been $2800 \text{ m}^3/\text{s}$.

The close association between alluvial terraces and debris fans was described by Howard and Dolan (1981). They found that fine-grained sand deposits form terraces of pre- and postdam age adjacent to debris fans throughout Grand Canyon. Alluvial deposits of postdam age were mapped, classified, and related to hydraulic conditions at rapids and debris fans by Schmidt and Graf (1990). They found that most of the alluvial deposits in Grand Canyon are in recirculation zones, or eddies, that form upstream and downstream of channel constrictions near active debris fans. Schmidt (1990) found that the alluvial depositional sites increase in size as discharge increases. These two studies show that channel hydraulics along the margin of a fan affect sedimentation through a wide range of discharge. Hence, development of segmented debris fans and accumulation of Colorado River alluvium are closely linked, as emplacement of the fans formed alluvial depositional sites.

Erosion of debris fans by the Colorado River was studied by Kieffer (1985, 1990), who developed a model describing the co-evolution of debris fans and rapids. Initially, the fan is enlarged by deposition of coarse debris-flow sediment that constricts the river channel, which is subsequently eroded by main-stem floods. Fan erosion and channel widening begins shortly after emplacement, the result of supercritical flow conditions in the newly constricted channel. Eventually, a large flood widens the channel substantially, producing subcritical flow conditions and establishing a stable channel configuration for that discharge level. Kieffer (1985) showed that debris fans are erodible and that erosion takes place at flow rates that have occurred historically. Erosional modification of fans, therefore, does not require extremely large floods.

DEBRIS FANS AND ALLUVIAL CHRONOLOGY, GRAND CANYON

TABLE 1. SURFACE-WEATHERING CHARACTERISTICS OF FAN-FORMING DEBRIS FLOWS, EASTERN GRAND CANYON, ARIZONA

Characteristic	Debris-flow age category		
	Younger	Intermediate	Older
Carbonate coatings, undersides of clasts	None	Stage I, discontinuous, thin, < 0.1 mm	Stage I, discontinuous to continuous, thin < 0.5 mm
Splitting, spalling, and granular disintegration of sandstone clasts	None	Slight	Common
Tafoni	None	Present	Present and well developed
Limestone-clast pitting*	None to incipient, < 1 mm	Present, 1.47 to 4.04 mm	Present, 4.74 to 9.97 mm
Rilling of limestone clasts	None	None	Present on 5 percent of clasts
Rock varnish, sandstone clasts	Absent to incipient on 50% of clasts	Present on 50%-100% of clasts, brown to dark brown	Well developed on all clasts, dark brown to black

*Average depth of solution pits measured with a depth micrometer, number of individual measurements (N) = 1156 and 1301 of intermediate-age and older, respectively. Measurements made on the surfaces of 149 and 96 intermediate-age and older clasts.

Studies of tributary streams demonstrate that debris flow is the principal means of sediment transport to the Colorado River throughout Grand Canyon (Webb et al., 1989; Melis and Webb, 1993; Melis et al., 1994). Debris flows originate in the steep headwaters of tributaries following prolonged or intense rainfall. In places, repeated photographs show the effects of debris-flow sedimentation in the river channel. Generally, deposition of the coarse sediment forms a debris fan that narrows the channel, forming a rapid where none existed or causing an existing rapid to become rockier and steeper (Cooley et al., 1977; Webb et al., 1988). These studies show that debris flows are relatively frequent in historical time, forming small debris fans in the channel and maintaining the rapids.

Briefly, the ongoing processes of debris-flow sediment transport and the relation of active debris fans to river hydraulics are reasonably well understood. However, the older debris fans and the chronology of interbedded main-stem alluvium have been studied only recently (Hereford et al., 1993; Hereford, 1993, in press). In this report, we discuss the geomorphology and age of nine tributary fans in eastern Grand Canyon (Fig. 1) and the relationship of the debris fans to the Holocene alluvial chronology of the Colorado River. The age of the deposits is important for understanding the time scale of debris-fan formation, erosion of fans by main-stem floods, and the age of the rapids. Ongoing studies indicate that seg-

mented fans of similar size, age, and morphology are present elsewhere in Grand Canyon where the bedrock channel is wide enough for accumulation and preservation of sediment.

Methods

The largest debris fans and terraces in Grand Canyon are too small to show adequately on 1:24 000 scale topographic maps. This limitation was overcome by producing large-scale base maps of the four areas shown in Figure 1. These maps range in scale from 1:1000 to 1:2000 and have a 1 m contour interval; they were produced photogrammetrically using low-altitude aerial photographs (Hereford et al., 1993). On these maps, portrayal of fan topography and related geomorphic features is adequate for surficial geologic mapping (e.g., see Hereford, 1993). The surficial deposits were classified by type, mapped, and dated where possible. The fans outside the mapped areas (Fig. 1) were studied in the field using low-altitude aerial photographs and 1:5000 scale topographic maps (Lucchitta, 1991).

Poor exposure and lack of organic material preclude direct dating of the coarse-grained debris-flow sediment. For this reason, qualitative and quantitative analysis of surface weathering was used to distinguish fan surfaces (or segments) at the nine debris fans (Fig. 1), thereby establishing the relative age and correlation of surfaces in the study area. The minimum date of the young-

est surfaces was established from historic photographs taken in 1890, which were supplied by Robert H. Webb (U.S. Geological Survey, Tucson, Arizona). The absolute age of a surface was then inferred from radiometric and archaeologic dating of alluvium associated with the debris fans as well as by dating of fine-grained debris-flow sediment interbedded with the alluvium. The stratigraphic relations demonstrate that the ages of the terrace-forming deposits bracket the ages of the debris-fan segments.

The age of the deposits as determined by radiocarbon assays is reported in calendar years to emphasize the close association between the surficial deposits and archaeologic remains. Calibration of radiocarbon years to calendar years was done with the Gronigen Radiocarbon Calibration Program (version of June 1991) using data current through 1989; the program was furnished by the U.S. Geological Survey Radiocarbon Laboratory (Reston, Virginia). In the calibration procedure, multiple dates are possible for a single sample because of secular radiocarbon fluctuations (Klein et al., 1982).

SEGMENTED DEBRIS FANS OF THE EASTERN GRAND CANYON

Geomorphology

Debris fans in eastern Grand Canyon consist of two major elements. The larger element is the broad surface of the fan itself, which is segmented into at least three surfaces of different ages. More than three surfaces are present locally, although we are unable to map them separately on 1:2000 scale maps. The deposits underlying the surfaces are referred to as the fan-forming debris-flow deposits, because the primary fan surfaces are developed on these deposits. The smaller element is an active debris-flow channel entrenched 2-5 m below the segmented surface that is partly filled with debris-flow deposits. These deposits form a small debris fan at the mouth of the channel. The deposits of the fan and entrenched channel are referred to as the channelized debris-flow deposits.

In eastern Grand Canyon, the preserved area of the fan-forming deposits is substantially larger than the area of the entrenched channel and its associated fan (Fig. 2). Typically, the area of the segmented fan surfaces is about six times larger than the area of the active debris-flow channels and related fans, based on the median ratio of fan




Figure 2. Area of debris fan and entrenched channel for selected tributaries in the study area (Fig. 1). Topographic boundary of the fans was identified on low-altitude aerial photographs. Area was measured on 1:5000 scale topographic maps of Lucchitta (1991). BC = Basalt Canyon; CAC = Cardenas Creek; CC = Comanche Creek; EC = Espejo Creek; LTC = lower Tanner Canyon; PC = Palisades Creek; UC = Unkar Creek; UPC = upper Palisades Creek.

Table 1). On the intermediate-age surface, rock varnish is on 50%–100% of the sandstone clasts, and limestone clasts are distinctly roughened with solution pits (Fig. 3B; Table 1). The undersides of clasts on the surface typically have a thin, very light gray to white discontinuous coating of calcium carbonate. On the older surface, up to 100% of the sandstone clasts have well-developed rock varnish; limestone clasts are distinctly and deeply pitted (Fig. 3C); and the undersides of clasts have a thin, mostly continuous coating of calcium carbonate. Sandstone clasts locally have honeycomb-like or cavernous weathering resembling tafoni (Fig. 3D). On the oldest surfaces, rillenkarren is on up to 5% of the clasts (Fig. 3E).

Solution pits on carbonate clasts, which are prominent on intermediate-age and older surfaces of Grand Canyon (Fig. 3; Tables 1 and 2), are thought to result mainly from biogenic weathering and solution by acidified rainfall. The metabolic activity of endolithic cyanobacteria, or blue-green algae, is probably the major cause of solution pits (Danin, 1983; Danin and Garty, 1983), although some controversy surrounds the significance of biogenic weathering (Cooke et al., 1993, p. 44). We have not tested for the presence of bacteria in eastern Grand Canyon; however, biogenic solution is reported from similar arid environments (Smith, 1988). The bacteria remain dormant while dry, but moisture from rainfall or dew causes photosynthesis that consumes CO_2 during the day; the excess is then released at night to the wet surface of the clast. This release of CO_2 plus water forms carbonic acid that slowly etches the surface of the clast.

The depth of solution pits is a quantitative method of distinguishing among the intermediate-age and older surfaces. A depth micrometer was used to measure the depth of several thousand solution pits on 149 intermediate-age and 96 older clasts (Table 1) distributed among the nine debris fans. Previously discussed topographic relations and surface weathering were used initially to identify the surfaces. Fifteen traverses were made on intermediate-age surfaces and 14 on the older surfaces. The number of clasts examined in a traverse ranged from two to ten and from two to nine in the intermediate-age and older categories, respectively. Average pit depth of all pits on the intermediate-age surfaces is 3.23 mm, and all pits measured on the older surfaces average 5.76 mm (Fig. 4A). These average depth mea-

to channel area. In certain cases, the subaerial extent of these channelized deposits may not coincide with the full extent of the debris flow, as much of the sediment can be deposited subaqueously in the channel (Melis and Webb, 1993; Melis et al., 1993). The smallest of the debris fans is upper Palisades Creek with total area of 10 100 m²; the largest is Unkar Creek with total area of 220 000 m² (upc and uc, respectively, Fig. 2).

Debris fans larger than about 10 000 m² with segmented surfaces are widespread in Grand Canyon wherever the bedrock channel is sufficiently wide, although the scarcity of large-scale maps precludes area measurements canyonwide. Large-scale topographic maps (Hereford and Thompson, 1994a, 1994b) show that debris fans at Nankoweap Creek and Little Nankoweap Creek in Marble Canyon and Granite Park Wash and 209 Mile Canyon in western Grand Canyon (river mile 52 and 209, respectively) have segmented surfaces and active channels.

The shape of debris fans is reach dependent (Melis and Webb, 1993); deep, narrow reaches such as upper Granite Gorge between river mile 77.5 and 117.8 (Schmidt and Graf, 1990) have insufficient space to accommodate large debris fans. At Crystal Creek fan in the upper Granite Gorge, the active channel is substantially larger than the older fan, as inferred from the large-scale map of Kieffer (1988). This geomorphology differs from the fans of eastern Grand Canyon and resulted from extensive erosion by the Colorado River that mostly removed the older fan surfaces.

In eastern Grand Canyon, the channelized and fan-forming debris-flow deposits are further subdivided according to age and topographic expression. The channelized debris-flow deposits consist of a younger unit that forms the active debris-flow channel and an older unit that forms one or more poorly to well-developed terraces in the entrenched channel. Both units were deposited by at least two debris flows in the past 100 yr, based on the relation of the deposits to Colorado River alluvium of known age (Hereford et al., 1993).

At least three fan-forming debris-flow deposits form the surface of segmented fans in the study area (Fig. 1) and other large debris fans in Grand Canyon. These surfaces parallel the underlying deposits and are contemporaneous with deposition; the deposits are referred to as the older, intermediate, and younger fan-forming debris flows or deposits, respectively. The surfaces are distinguished from each other by relative topographic position and surface-weathering characteristics. Generally, the older surfaces have the highest elevation and are farthest from the river. The degree of surface weathering differs among the three surfaces, as shown in Table 1. The stage of development of the characteristics listed in Table 1 is generally time dependent (Smith, 1994), which suggests that the three surfaces are of different relative ages.

Characteristics typical of the surfaces are illustrated in Figure 3. The younger surface has weakly developed or no discernible rock varnish and the limestone clasts appear fresh with little surface roughness (Fig. 3A;




Figure 3. Photographs showing weathering of fan surfaces. Scale is 15 cm long in A, D, and E; 10 cm in B and C. A–D, Palisades Creek fan. (A) Younger debris-flow surface with light-colored clasts without surface pitting. (B) Intermediate-age surface with rock varnish and pitted-limestone clast above scale. (C) Older surface with well-developed rock varnish, pitting of limestone clast (below scale), and granular disintegration of light-colored sandstone clast (right of scale). (D) Sandstone clast with tafoni weathering on older surface. (E) Limestone clast with rillenkarren, older surface Cardenas Creek.

measurements show a clear distinction between intermediate-age and older surfaces (Fig. 4B). Average pit depth of the intermediate-age surfaces was shallower than 4 mm in 95% of the cases; whereas pit depth of the

older surface was deeper than about 4.5 mm in 95% of the cases. Finally, maximum depth per traverse also shows a clear distinction between the surfaces (Fig. 4C). Ninety-five percent of intermediate-age surfaces have

maximum pit depth shallower than about 7.5 mm, whereas maximum depth on the older surfaces is deeper than about 7.5 mm in 95% of the cases.

The rate of pit deepening was estimated

TABLE 2. OBSERVED AND POSSIBLE STRATIGRAPHIC RELATIONS BETWEEN DEBRIS-FLOW DEPOSITS AND SURFACES WITH TERRACE-FORMING ALLUVIUM, EASTERN GRAND CANYON

Debris-flow age category	Stratigraphic relation		
	Interbedded	Alluvium overlaps debris flow	Debris flow overlies alluvium
Younger	[umt]*	[umt]	umt
Intermediate	ap [†]	ap [umt]	sa
Older	sa	[sa, ap, umt]	[sa]

Note: sa = striped alluvium; ap = alluvium of Pueblo II age; umt = upper mesquite terrace.
 *Brackets indicate stratigraphic relation possible, but not observed.
 †Observed stratigraphic relation.

from pit depths on limestone boulders used to construct an ancient check dam in the Nankoweap Creek area of Marble Canyon. Based on dated ceramics, this small dam was built by the Kayenta Anasazi in Pueblo II time (A.D. 1000–1150). Using A.D. 1075 as the construction date, the dam is 0.915 ka. Maximum pit depth is 3.58 mm and average depth is 1.93 mm. The rate of deepening is about 4 (3.91) and 2 (2.11) mm/1000 yr for maximum and average depth, respectively. The less deeply pitted intermediate-age fan surfaces of eastern Grand Canyon (Fig. 4) are contemporaneous with the dam.

Another study of solution pits estimated rate of pit deepening using maximum depth measured on the surface of limestone used to construct dated archaeological structures in Israel (Danin, 1983; Klein, 1984). These studies found that average maximum depth increases by 5 mm/1000 yr, which is more than the 4 mm/1000 yr estimated for eastern Grand Canyon. This reduced rate probably results from climate and different lithology. Grand Canyon is warmer and drier than Israel, which should reduce the rate substantially. Average annual temperature at Phantom Ranch in eastern Grand Canyon is 21 °C and average rainfall is 211 mm, whereas at the Middle East archaeological sites, annual temperature is 17–18 °C and annual rainfall is 611 mm (Danin, 1983; Sellers and Hill, 1974, p. 372–373). Lithologically, the limestone clasts used in the check dam are heterogeneous compared with the relatively pure limestones used in the tombstones and large archaeological structures studied by Danin (1983) and Klein (1984).

We are presently reluctant to calculate the age of the surfaces using the 2 or 4 mm/1000 yr rate, as the functional relation between time and average or maximum pit depth is unknown in eastern Grand Canyon. Nevertheless, debris fans with limestone clasts having pit depth similar to the check

dam are about 1 ka. Most of the intermediate-age surfaces probably predate Pueblo II time, or A.D. 1000–1150 (Fig. 4).

Degree of patination expressed by the darkness of sandstone clasts is related to limestone-clast pit depth (Fig. 5). Varnish darkness (Bull, 1991, p. 63–64), the mean of value and chroma, of sandstone clasts decreases with increasing average pit depth. Surfaces with deeply pitted limestone clasts have the darkest sandstone clasts, which is also indicated in Table 1. The patination on these surfaces (Figs. 3 and 5; Table 1) developed between Pueblo II time and somewhat before 2.8 ka, which is the likely maximum age of the fans as discussed in a following section of the report.

This rate of patination and weathering is difficult to compare with other desert areas because of different clast lithology, local climate effects peculiar to eastern Grand Canyon, and regional climate differences. The patinated clasts examined here are sandstone; whereas alluvial fans of the deserts in the nearby southern Basin and Range province are primarily volcanic, plutonic, and metamorphic (Wells et al., 1987; McFadden et al., 1989; Bull, 1991, p. 86; Reheis et al., 1993). These indurated rocks probably weather slowly compared with the sandstone and limestone of debris fans in eastern Grand Canyon. Also, microclimate of the river corridor as it relates to weathering and varnish formation is affected by close proximity of the Colorado River, which increases humidity locally.

Regional climate of eastern Grand Canyon differs from climate of southern Basin and Range. Although temperature is similar to low elevation sites in the Basin and Range, annual rainfall of Grand Canyon is nearly twice that of Baker, California, in the eastern Mojave Desert and Yuma, Arizona, in the Sonoran Desert (National Climate Data Center, and Sellers and Hill, 1974,




Figure 4. Box-plot statistical summaries of pit-depth measurements of intermediate-age and older surfaces. Shaded box is 25th through 75th percentile, median is shown with solid line and average is shown with dotted line, capped-vertical bar is range of 5th through 90th percentile, and solid circles are the 10th and 95th percentiles, respectively. (A) All measurements. (B) Average pit depth by traverse. (C) Maximum depth by traverse.

p. 584–585). High-elevation sites in the southern Great Basin are also drier and cooler than eastern Grand Canyon. For example, Beatty, Nevada, receives 155 mm/yr and average annual temperature is 15 °C; Tonopah, Nevada, averages 136 mm/yr and average temperature is only 11 °C.




Figure 5. Darkness of varnish on sandstone clasts as a function of pit depth. Darkest clasts are associated with deeply pitted limestone clasts; r = correlation coefficient.

Fan Morphology

The distribution of the fan-forming deposits has considerable variation that affects the shape of the fans in eastern Grand Canyon. Figure 6 illustrates the two main types of fan morphology. At the Palisades Creek fan (Fig. 1), the older fan-forming deposits are preserved at the apex and near the eroded distal margin close to the river (Fig. 6A). Intermediate-age deposits form most of the fan surface. Below the apex of the fan, intermediate-age deposits cover older deposits; whereas the intermediate deposits are inset below the older deposits at the fan apex. The younger debris-flow deposits are mainly on the south side of the fan, where the fine-grained distal facies of the intermediate-age and younger debris flows are interbedded with Colorado River alluvium. Older and younger channelized deposits are in the relatively deep main channel of Palisades Creek and in the smaller channel north of the creek, respectively.

The surficial geology of the lower Tanner Canyon debris fan is illustrated in Figure 6B. This fan lacks the distinctive radial shape of the Palisades Creek fan. The older debris-flow deposits are at the west and east margins of the fan and in the central portion where they form a ridge in a broad channel-like depression. This channel, which is 110 m wide and 2–3 m below the surface of the older debris flow, contains the intermediate-age and younger fan-forming deposits and the channelized deposits. The younger fan-forming deposit crops out on the west side of

the fan, where it forms a low ridge between topographically higher outcrops of older and intermediate-age deposits. On the west side of the outcrop, the younger debris-flow sediment flowed across an alluvial terrace that is extensively covered with sand dunes. Subsequent eolian activity has partly covered the deposit, producing the outlier at the westernmost outcrop. The older and younger channelized deposits occupy relatively narrow and deep channels entrenched into the intermediate and younger surfaces. The older channelized debris flow is interbedded with alluvium that dates from A.D. 1922 to 1958, indicating the debris flow occurred during this period. The younger channelized debris flow was deposited in A.D. 1983 or 1984, based on aerial photographs taken in 1984 and the relation of the deposits to alluvial sand deposited in summer 1983.

Sand at lower Tanner Canyon and Palisades Creek forms several discontinuous terraces around the distal margins of the fans that range in age from prehistoric to postdam. The sand is extensively reworked by eolian activity, forming coppice dunes that cover a large part of the underlying alluvium. The dunes are not indicated in Figure 6, as they obscure the relation between the alluvial sand and the debris-flow deposits. The irregular, digitate contact between terrace-forming alluvium and the older and intermediate-age debris-flow surfaces results largely from onlap; whereas the contact with the younger deposits results from deposition of the debris flow on alluvium.

Stratigraphy

The channelized and fan-forming debris-flow deposits are broadly similar in composition. Both units consist primarily of clast-supported angular and subangular to subrounded clasts of local bedrock ranging in size from granules to boulders that are up to 3–5 m on an edge. The clasts are a mixture of resistant Paleozoic sandstone, limestone, and dolomite, which are present in the walls of the canyon and steep talus slopes beneath the cliffs.



The debris-flow matrix is a poorly sorted mixture of clay to coarse sand and granule gravel. Large boulders up to 1–3 m on an edge occur near the apex of the fans, although boulders this large are also present at the margin of the fans. Fluvial gravel of tributary origin is locally interbedded with the debris-flow sediment. The fluvial gravel typically consists of subrounded weakly im-

bricated pebble to small boulder-size clasts with minor coarse sand matrix; these gravels are distinctly finer grained and relatively well sorted compared with debris-flow gravel.

Fan-forming debris-flow deposits are exposed in the south side of the active debris-flow channel of Palisades Creek (Fig. 1). This section of the proximal to medial portion of the fan (Fig. 7A) is unusually well exposed and shows the stratigraphic relations among the deposits; the location of the section on the debris fan is shown in Figure 6A. Figure 7B is a stratigraphic section of the older through younger fan-forming deposits. The deposits consist of four beds of gravelly debris-flow sediment interbedded with four beds of fluvial gravel derived from Palisades Creek. The composition and texture of these beds are similar to the debris-flow and fluvial gravels described above. The fluvial beds are probably contemporaneous with the debris-flow beds. Historic debris flows are typically preceded or followed by streamflow, according to Webb et al. (1988, p. 12; 1989) and Cooley et al. (1977, p. 12).

The basal and upper contacts of the debris-flow beds occur over 1–5 cm and are sharp and scoured. Evidence of weathering and soil development is lacking along each of the seven bedding planes; evidence of long-term exposure and weathering at the surface of the younger debris flow (dfy, Fig. 7B) is also absent, probably because it was deposited only slightly more than 100 yr ago. The large clast (dfi, Fig. 7B) is part of the intermediate-age deposit, as shown by field relations immediately west of the cross section. The clast is patinated at the surface and has a thin, discontinuous coating of light-colored calcium carbonate extending 5–10 cm beneath the surface (Fig. 7A). Weathering of this clast, which happened after deposition, was preserved because the upper portion of the clast was above the abrasive effects of subsequent debris-flow activity.

The absence of buried soils or evidence of long-term exposure is not expected given the age of the deposits, which is discussed in a following section of the report. The intermediate-age bed is about 1300 yr older than the younger deposit, and the older debris-flow beds are possibly 1000 yr older than the intermediate-age bed (Fig. 7B). This lack of soil development implies that deposition of the debris-flow beds was accompanied by erosion of the underlying bed, which removed evidence of weathering and exposure. This conclusion is supported by evi-



EXPLANATION

Channelized debris-flow deposits

- dcy Younger
- dco Older

Fan-forming debris-flow deposits

- dfy Younger
- dfi Intermediate age
- dfo Older

Terraces and coppice sand dunes

- Sand and minor gravel, undifferentiated, mostly Colorado River alluvium and eolian sand reworked from alluvium

Erosional scarp

Reconstructed margin of intermediate-age debris fan

Figure 6. Surficial geologic maps of segmented debris fans. (A) Moderately truncated Palisades Creek fan showing radiating pattern of fan-forming debris-flow deposits, reconstructed outline of intermediate-age debris-flow deposits, and trace of erosional scarp at base of fan. (B) Severely truncated lower Tanner Canyon fan showing two erosional scarps at margin of older and intermediate-age deposits, respectively.




Figure 7. Interbedded debris-flow and fluvial gravel, south side of Palisades Creek. (A) Photograph of the deposits; scale is 1.4 m long with 20 cm divisions. (B) Measured stratigraphic section. Older, intermediate age, and younger deposits are labeled dfo, dfi, and dfy, respectively. See Figure 6A for location of section.

dence that debris flows in steep channels can be erosive, exerting six times more shear stress than streamflow (Costa, 1984). Moreover, evidence from historic debris flows in Grand Canyon shows that passage of the flood wave was locally erosive (Cooley et al., 1977; Webb et al., 1988, 1989).

The stratigraphy of the Palisades Creek fan indicates that the fan resulted from at least four fan-forming debris flows. Three of these are distributed across the medial to distal surface of the fan (Fig. 6A), where the surfaces have the distinctive weathering characteristics listed in Table 1. The older debris flow consists of two beds (Fig. 7B)

that are indistinguishable on the surface. Either the two beds are closely related in time or the older bed is not exposed at the surface. Three temporally distinct surfaces are also present on debris fans elsewhere in eastern Grand Canyon. These surfaces are equivalent to those at Palisades Creek based on the degree of surface weathering.

Erosional Truncation of Debris Fans

Geologic and topographic maps of the debris fans reveal the extent of erosion by the Colorado River, which in turn affects how the fans aggraded. The distribution of the

fan-forming deposits and the shape of the upper part of the Palisades Creek fan resemble the radiating pattern typically associated with alluvial fans (Hooke, 1987). An erosional scarp 2–3 m high at the toe of the fan (Fig. 6A), however, is evidence that the Colorado River eroded and partly truncated the fan. Reconstruction of the intermediate-age deposit suggests that the near-channel margin of the fan was eroded 50–60 m to the east, forming the scarp (Fig. 6A). The reconstruction is based on the assumption that the intermediate-age debris flow initially extended across the entire radius of the fan. The scarp truncates the older and intermediate-age debris-flow deposits, and it is overlapped by alluvium that is younger than A.D. 1200. Therefore, erosion of the scarp occurred between A.D. 660 and 1200. Most of this fan lies above the level of pre-historic alluvial deposits and historic floods. In addition, the fan lacks well-developed inset relations among the surfaces and it appears to have aggraded vertically (Figs. 6A and 7).

The size of the flood that eroded the scarp and widened the channel is uncertain, but it was probably large because (1) the top of the scarp is 5 m above present postdam high-water level (2800 m³/s), (2) channel width at the rapid measured to the base of the scarp is 155 m compared with 120 m at the present high-flow level, and (3) the deposits contain clasts up to 2–3 m in diameter. An alluvial terrace that postdates both the scarp and debris flow overlaps the scarp locally. This terrace is above the level of a still-younger terrace that was probably deposited by the largest flood of the historic period in July 1884 with peak flow rate of 8500 m³/s (Hereford, 1993). Thus, the flood that initially eroded the scarp was probably somewhat larger than 8500 m³/s, which is consistent with Kieffer (1985), who estimated that flow rates between 8500 to 11 300 m³/s are necessary to widen the channel substantially and to erode the typical debris fan.

Unlike the Palisades Creek fan, the lower Tanner Canyon fan is severely truncated and retains little of the fan shape (Fig. 6B). Most of the lower Tanner Canyon fan lies within the range of pre-historic floods. Pre-historic flood-related alluvial deposits are downstream of the fan at elevations of 808–812 m; the elevations of the two fan segments are slightly higher (810–815 m). The intermediate and older debris-flow deposits are both truncated, having scarps with maximum relief of 3 and 5 m, respectively (Fig. 6B). The scarps were produced by at

least two main-stem floods; the first flood or floods occurred after deposition of the older debris flow. Truncation of the fan margin steepened the overall fan gradient, causing entrenchment of a channel in the central portion of the fan. The intermediate-age flow was subsequently deposited in a channel position 2–3 m below the surface of the older deposit. The intermediate-age flow partly filled the channel and extended the fan beyond the eroded margin of the older deposits. The second flood truncated the fan margin formed by the intermediate-age deposits (Fig. 6B). The fan has not aggraded vertically; rather it has developed mainly by aggradation of inset segments. The inset segments result from one or more floods that cut into the medial portion of the fan. This lowered the base level of the fan leading to entrenchment of the surface and emplacement of subsequent debris flows at a lower level.

The topographic maps of Lucchitta (1991) and Hereford et al. (1993) show that the Unkar Creek, Cardenas Creek, Comanche Creek, Espejo Creek, and upper Palisades Creek fans (Fig. 1) are moderately truncated, as they have an approximate fan-like shape that broadly resembles the Palisades Creek fan. In contrast, the Basalt Creek and Tanner Canyon fans are severely truncated, with steep scarps up to 5 m high that surround the margin of each fan. These different morphologies are related to the age of the fan, the course of the river around the fan, and the elevation of the fan relative to flood level.

A severely truncated fan could be older than a moderately truncated fan, as the older fan has been subjected to a larger number of main-stem floods. The fans of eastern Grand Canyon, however, are of broadly similar age as indicated by similar weathering characteristics (Table 1). This suggests that the position of a fan relative to the river influences fan erosion. Moderately truncated fans are in relatively straight reaches where the river is essentially parallel with the distal-fan margin. At severely truncated fans, the river flows into and around the fan margin (lower Tanner and Tanner Canyon) or it flows entirely around the fan margin (Basalt Creek; Figs. 1 and 6). In these situations, the river is particularly effective at eroding the fan because it flows directly into the upstream margin of the fan, or the river channel completely surrounds the fan margin.

The elevation of a fan relative to the river also controls the extent of erosional modi-

fication, at least in the case of the Palisades Creek and lower Tanner Canyon fans. The apex of the moderately truncated Palisades Creek fan lies well above flood levels, suggesting that the volume of sediment was larger than the river was able to remove during recent millennia. On the other hand, most of the severely truncated lower Tanner Canyon fan lies within the level of prehistoric floods, and the fan was relatively low and easily eroded. This difference between high and low elevation fans is evidently related to the slope or gradient of the fan, which in turn is a function of basin relief, lithology, and area (Cooke et al., 1993, p. 177–178).

ALLUVIAL CHRONOLOGY AND AGE OF THE SEGMENTED DEBRIS FANS

Abundant radiocarbon assays and archaeological remains were used to date the late Holocene alluvial deposits of the Colorado River. Direct dating of the coarse-grained debris-flow deposits forming the segmented fans has not been possible because of poor exposure and lack of organic material. The fan-forming debris-flow deposits are inferred to be late Holocene, based on radiocarbon dating of fine-grained debris-flow deposits, the relation to dated Colorado River alluvium, and the association with dated archaeological remains. Generally, the debris fans are younger than Pleistocene, as inferred from their topographic position below terrace-forming river gravel of known late Pleistocene age (Hereford, 1993, in press). Calcic soils on the terraces were dated in eastern Grand Canyon by Machette and Rosholt (1991) using the uranium-trend disequilibrium method.

These minimum dates suggest that the two lowest gravel terraces are 15 ± 5 and 40 ± 24 ka, respectively, which is latest Pleistocene. Moreover, the debris fans occupy a bedrock channel that is lower, narrower, and of different alignment than the channel with late Pleistocene deposits. This suggests that the bedrock channel was downcut and widened substantially after deposition of the terrace-forming gravels and before accumulation of the debris fans and associated alluvium.

Alluvial Chronology

Three late Holocene terraces and related alluvial deposits are stratigraphically related to the segmented debris fans of eastern Grand Canyon. From oldest to youngest, these deposits are referred to as the striped alluvium (sa), the alluvium of Pueblo II age (ap), and the alluvium of the upper mesquite terrace (umt). The alluvial deposits form discontinuous, poorly preserved terraces and terrace-like features adjacent to and bordering the debris fans. Observed stratigraphic relations between the debris-flow deposits and the alluvial terraces are summarized in Table 2. Basically, the debris-flow deposits are interbedded with, overlie, or are overlapped by the alluviums.

Figure 8 illustrates schematically the geomorphology and geology of the three terraces, the height of the terraces above the river, and the relation to streamflow levels. This figure is a composite developed from exposures in eastern Grand Canyon. The full suite of terraces is not present at any single cross section and the terraces are not paired. Younger terraces are topographically lower than older terraces; however, the




Figure 8. Generalized cross section showing geomorphic and geologic relations of late Holocene terrace-forming alluvium and positions of terraces relative to regulated streamflow levels, eastern Grand Canyon. Alluvium and terraces associated with segmented debris fans: sa = striped alluvium; ap = alluvium of Pueblo II age; umt = upper mesquite terrace.

stratigraphic relations among the deposits indicate that the units partly overlap (Fig. 8; Hereford, in press, Fig. 3).

The physical and time stratigraphy of alluvial and debris-flow deposits and the archaeological chronology of eastern Grand Canyon are shown in Figure 9. The radiocarbon dates shown in Figure 9 are listed in Table 3, which gives the location, sample material, stratigraphic context of the samples, and calibrated dates. Several of the dates in Figure 9 overlap mapped stratigraphic units, which suggests that the units are not clearly separated in time. Inset topographic relations and stratigraphic discontinuities demonstrate that the units are

separated by erosional unconformities (Fig. 8; Hereford et al., 1993; Hereford, 1993). These physical relations were used to identify stratigraphic units from which carbon samples were collected; thus each unit should yield temporally distinct dates. The overlapping dates, therefore, result largely from limitations of the ¹⁴C dating method; specifically, secular variation of ¹⁴C fluctuations, the inherent precision of ¹⁴C measurements, and uncertainties regarding sample provenance (Taylor, 1987).

Geologic and archaeological evidence suggests that the duration of each hiatus was up to several centuries. The absence of buried soils, however, indicates that the interval of

nondeposition was brief relative to the time needed for soil development. The archaeological record shows that major cultural adjustments occurred during the two periods of erosion and nondeposition, suggesting that substantial time elapsed in each case. The striped alluvium is aceramic and lacks any structures more complex than simple hearths. In contrast, complex dwelling structures and a wide variety of ceramic material are associated with the alluvium of Pueblo II age. The alluvium of the upper mesquite terrace does not contain material of Anasazi affiliation, indicating that the Anasazi abandoned the Grand Canyon before deposition of the alluvium.




Figure 9. Radiocarbon dates calibrated to calendar years arranged by stratigraphic unit showing relations among physical stratigraphy of late Holocene alluvium, archaeological chronology, and time stratigraphy of alluvium and debris-flow deposits. Archaeologic chronology of Altschul and Fairley (1989).

TABLE 3. RADIOCARBON DATES OF ALLUVIUM AND OF DEBRIS-FLOW RELATED DEPOSITS AND ARCHAEOLOGIC FEATURES, EASTERN GRAND CANYON, ARIZONA

Sample number		Location*		Material	Date (yr B.P.)	Calendar date†	Description	
No.	Field number§	Lab. number#	Latitude (DMS)**					Longitude (DMS)**
Striped alluvium								
1	TWRC 2	AA-5781	35 05 55	111 50 10	Charcoal	1870±70	30 B.C.-A.D. 260 A.D. 290-330	Striped unit
2	TWRC 14	β-51480	ibid.	ibid.	Charcoal	2330±100	770-190 B.C.	Flake zone, base of exposure
3	TWRC 3	W-5285	35 05 57	111 50 10	Charcoal	2160±40	370-280 B.C. 260-110 B.C.	Hearth, base of exposure
4	TWRC 4	W-5287	ibid.	ibid.	Charcoal	2150±30	360-290 B.C. 250-110 B.C.	Hearth, base of exposure
5	TWRC 8	AA-5785	ibid.	ibid.	Charcoal	1710±70	A.D. 130-450 A.D. 490-500 A.D. 510-530	Hearth, top of unit
6	TWRC 15	AA-9527	35 05 05	111 49 55	Charcoal	1610±90	A.D. 240-620	Top of unit
7	TWRC 15-1	β-35125	35 05 05	111 50 05	Charcoal	2170±70	390-90 B.C. 70-50 B.C.	Base of exposure
8	BCRC 1	AA-5789	35 05 28	111 50 59	Charcoal	2120±110	400 B.C.-A.D. 80	Base of exposure
Alluvium of Pueblo II age								
9	PCRC 5	W-5289	35 08 11	111 48 55	Charcoal	1170±60	A.D. 690-700 A.D. 710-750 A.D. 760-980	PII unit
10	PCRC 14	W-5373	ibid.	ibid.	Driftwood, outer rings	880±50	A.D. 1030-1250	Wood associated with structure in PII unit
11	PCRC 6	W-5291	35 08 28	111 48 52	Charcoal	1140±60	A.D. 720-730 A.D. 770-1010	Covered by slopewash
12	LCRC 1	W-5308	37 08 21	111 49 05	Charcoal	900±80	A.D. 1000-1270	Base of hearth
13	LCRC 2	W-5309	ibid.	ibid.	Charcoal	950±80	A.D. 900-910 A.D. 950-1250	Top of hearth
14	ECRC 1	AA-5785	37 07 15	111 49 23	Charcoal	970±90	A.D. 890-1240	Cultural horizon
15	ECRC 2	AA-5787	ibid.	ibid.	Charcoal	1050±60	A.D. 820-830 A.D. 860-1050 A.D. 1080-1120 A.D. 1140-1160	Cultural horizon

Age of Debris-Fan Surfaces as Inferred from Age of Late Holocene Terraces

The older debris-flow deposits of eastern Grand Canyon are partly equivalent in age to the striped alluvium. This alluvium consists of light-colored sand of Colorado River origin interbedded with pebble to small-cob-

ble gravel of red Dox Formation; these gravel interbeds form the distinctive red stripes that are characteristic of the unit. The alluvium is in the Tanner Canyon and lower Tanner Canyon areas (Fig. 1) where eight radiocarbon dates suggest that deposition occurred from about 770 B.C. until around A.D. 300 (Fig. 9; Table 3). The allu-

vium began to accumulate before 400 B.C. (samples 4, 7, and 8), or even before 770 B.C., as suggested by sample 2. The older debris-flow deposit is interbedded with the striped alluvium at an outcrop near the extreme west end of the lower Tanner Canyon area. Thirty meters south of this outcrop, the deposit forms the surface of a debris fan

DEBRIS FANS AND ALLUVIAL CHRONOLOGY, GRAND CANYON

TABLE 3. (continued)

Sample number			Location*		Material	Date (yr B.P.)	Calendar date†	Description
No.	Field number‡	Lab. number#	Latitude (DMS)**	Longitude (DMS)**				
16	ECRC 3	W-5443	35 07 05	111 49 30	Charcoal	970±80	A.D. 890-930 A.D. 930-1230	Cultural horizon
17	TWRC 5	AA-5782	35 05 58	111 50 10	Charcoal	770±90	A.D. 1040-1320 A.D. 1350-1390	PII? unit
18	TWRC 6	AA-5783	ibid.	ibid.	Charcoal	1250±130	A.D. 550-1020	PII? unit
Alluvium of upper mesquite terrace								
19	PCRC 3	W-5255	35 08 29	111 48 52	Mesquite pith	310±150	A.D. 1410-1890	Bush rooted on PII unit covered by sand
20	PCRC 4	W-5288	35 08 11	111 48 55	Driftwood, outer rings	190±40	A.D. 1640-1700 A.D. 1720-1830 A.D. 1830-1880	Sand on PII unit, pre-dates 1890
21	LCRC 3	W-5310	37 08 21	111 49 05	Charcoal	560±80	A.D. 1270-1460	Hearth
22	LCRC 7	W-5404	ibid.	ibid.	Charcoal	840±70	A.D. 1040-1270	Middle of unit
23	LCRC 9	W-5371	ibid.	ibid.	Charcoal	630±120	A.D. 1050-1080 A.D. 1120-1140 A.D. 1160-1510	Cultural horizon
24	LCRC 10	AA-9525	ibid.	ibid.	Charcoal	240±90	A.D. 1470-1890	Base of debris flow, upper part of unit
25	LCRC 11	W-5372	ibid.	ibid.	Mesquite pith	550±80	A.D. 1280-1470	Plant rooted on contact with PII unit
25	C:13:10 M1	W-5259	35 05 23	111 52 15	Mesquite pith	250±100	A.D. 1460-1890	Umt unit
27	C:13:10 M2	W-5251	ibid.	ibid.	Mesquite pith	300±50	A.D. 1460-1670 A.D. 1780-1790	Umt unit
Intermediate-age debris-flow related deposits and archeologic features								
28	PCRC 11	β-51470	35 08 11	111 48 55	Charcoal	1410±120	A.D. 390-890	Base of debris-flow distal facies
29	PCRC 12	β-51470	ibid.	ibid.	Charcoal	1380±140	A.D. 390-960	Top of debris-flow distal facies
30	TWRC 16	W-5440	35 05 03	111 49 45	Mesquite pith	570±50	A.D. 1290-1430	Tree rooted on debris-flow surface, minimum date

that has weathering characteristics similar to the older fan surfaces elsewhere in eastern Grand Canyon (Table 1). These relations indicate that the older debris-flow deposits in this area, and presumably elsewhere in eastern Grand Canyon, are as old as the striped alluvium.

In eastern Grand Canyon, deposits with intermediate-age surface characteristics are interbedded with and overlapped by alluvium of Pueblo II age (Table 2), which is present at or near the large debris fans (Fig. 1). This suggests that the intermediate-age deposits in this region are somewhat

older than to partly contemporaneous with the alluvium. The alluvium is named for the abundant Anasazi cultural remains of the Pueblo II period (A.D. 1000–1150), although material of the Pueblo I period (A.D. 800–1000) is present locally near the base of the alluvium, and early Pueblo III (A.D. 1150–

TABLE 3. (continued)

Sample number			Location*		Material	Date (yr B.P.)	Calendar date†	Description
No.	Field number‡	Lab. number#	Latitude (DMS)**	Longitude (DMS)**				
31	TWRC 17	W-5442	35 05 09	111 49 48	Charcoal	700±70	A.D. 1180-1190 A.D. 1210-1400	Hearth in sand deposited on debris flow, minimum date
32	LTWRC 1	W-5438	35 05 33	111 50 39	Charcoal	770±70	A.D. 1040-1100 A.D. 1110-1150 A.D. 1150-1300 A.D. 1350-1380	Hearth in sand deposited on debris flow, minimum date

*Latitude and longitude from Lucchitta (1991), Hereford and others (1993), and Hereford (1993).

†95% confidence interval in calendar years of the radiocarbon date, which was calibrated to calendar years using relations developed through measurement of ^{14}C activity of dendrochronologically dated wood (Klein and others, 1982). Multiple dates are possible because of atmospheric ^{14}C fluctuations.

‡TW = Tanner Canyon; BC and LTW = lower Tanner Canyon; PC = Palisades Creek; LC = Lava Canyon; EC = Espejo Creek; C:13:10 = upper Unkar; also see Figure 1.

#AA = accelerator mass spectrometry method done at the National Science Foundation Accelerator Facility, University of Arizona, by Meyer Rubin; β = Beta Analytical, Inc., Miami, Florida; WW = U.S. Geological Survey Radiocarbon Laboratory, Reston, Virginia.

**DMS = Degrees, minutes, seconds.

1200) material is on the surface (Hereford et al., 1993). Based on archaeological remains and ten radiocarbon dates (Fig. 9; Table 3), this alluvium accumulated between about A.D. 700 and 1200.

Additional dates were obtained from intermediate-age surfaces at Tanner Canyon and lower Tanner Canyon (Fig. 1). These minimum dates are from two hearths constructed in reworked alluvial sand deposited on the surface of the debris flow and from the inner rings of a mesquite tree rooted on the surface (Table 3, samples 31 and 32, and sample 30, respectively). At lower Tanner Canyon, the intermediate-age surface is older than A.D. 1040–1380, and at Tanner Canyon the surface predates A.D. 1180–1400 based on the date of the hearths.

The younger debris-flow deposits postdate the alluvium of Pueblo II age, as they are graded to a lower topographic level. Moreover, the debris-flow deposits do not contain Anasazi cultural remains, indicating that the younger deposits postdate A.D. 1200, which is the terminal date of Anasazi occupation of eastern Grand Canyon (Jones, 1985; Altschul and Fairley, 1989). The younger deposits are mostly equivalent to the alluvium of the upper mesquite terrace, which is present discontinuously throughout eastern Grand Canyon. This alluvium dates from about A.D. 1400 to 1880, based on nine radiocarbon dates (Fig. 9; Table 3). At Palisades Creek, the younger debris-flow deposit overlies the upper mesquite terrace, suggesting that it postdates

A.D. 1880. The debris-flow deposits are probably not younger than A.D. 1890. Portions of the Palisades Creek and Basalt Creek fans are in photographs (Fig. 1; Robert H. Webb Stanton numbers 385 and 394) taken in January 1890 by Robert B. Stanton during an expedition to map a railroad in Grand Canyon (Smith and Crampton, 1987). The fan surface in each case is smooth and fresh appearing, suggesting that a debris flow had occurred recently.

Age of the Debris-Flow Distal Facies

At the southern margin of the Palisades Creek fan, the thin bedded, relatively fine grained distal facies of the intermediate-age and younger fan-forming deposits were dated radiometrically. The stratigraphy at this locality consists of four beds of alluvial sand interbedded with the distal facies of three debris flows, as shown in Figure 10. The debris-flow deposits are a distinctive moderate orange pink and moderate reddish orange, the colors typical of debris-flow matrix exposed in Palisades Creek. From oldest to youngest, gravel content is 29%, 45%, and 2%, respectively. With the exception of widely scattered small boulders, the gravels are typically granule to small-cobble size and the gravel is matrix supported. The matrix is very poorly sorted medium sand with average silt and clay content of 25%.

Although they differ substantially in grain size and thickness, these fine-grained deposits are equivalent to the previously discussed

debris-flow gravel beds exposed in Palisades Creek (Fig. 7). The distal facies of the younger debris flow traces continuously up the fan surface to the medial portion of the fan at the outcrop in Palisades Creek (Fig. 6A). Clasts in the deposit become progressively larger and bed thickness increases substantially in the upslope direction. Intermediate-age and older distal facies undergo the same transition in grain size and thickness, although the transition is not exposed continuously on the surface.

Dateable material was found at the base and top of the intermediate-age debris-flow bed and in the two overlying alluvial sand units. Radiocarbon dates indicate that the intermediate-age debris flow occurred about A.D. 660, which is the median date of the two samples bracketing the deposit (Fig. 10; samples 28 and 29, Table 3). Deposition occurred before A.D. 1000, as the bed is the occupation surface of an early Pueblo II site. The sand overlying the intermediate-age bed yielded dates typical of the alluvium of Pueblo II age, that is about A.D. 700–1200. The upper alluvial sand bed (umt, Fig. 10) contains a limb or trunk of pine driftwood that was fresh appearing and fragrant when sampled. The outermost 5–10 growth rings of the driftwood were dated radiometrically (Table 3, sample 20), yielding three calibrated dates of A.D. 1540–1700, 1720–1830, and 1840–1880. Thus, radiocarbon dates show that the younger debris-flow deposit at this locality postdates A.D. 1540–1880, and




Figure 10. Cross section at southern margin of Palisades debris fan showing stratigraphic position of radiocarbon samples and alluvium interbedded with debris-flow deposit distal facies. Map units: ec = eolian deposit; umt = upper mesquite terrace; ap = alluvium of Pueblo II age; dfy = younger debris-flow deposits; dfi = intermediate-age debris-flow deposit; dfo = older debris-flow deposit; sa? = striped alluvium. See Figure 6A for location of section.

the Stanton photographs show that it is older than A.D. 1890.

Although the coarse-grained fan-forming debris-flow deposits of eastern Grand Canyon could not be dated directly, the relation of the deposits to dated alluvium suggests that the debris-flow deposits began to accumulate from about 770 B.C. until shortly before A.D. 1890. The debris fans, therefore, have been in place for at least 2800 yr. The older deposits date from 770 B.C. until sometime before A.D. 660, assuming that the dates from lower Tanner Canyon and Palisades Creek are representative. These older deposits coincide with the late Archaic through Basketmaker II periods of Southwest archaeology. Deposits of intermediate age date from A.D. 660 to as late as 1200, which is coincident with the Basketmaker III through early Pueblo III periods. The younger deposits postdate A.D. 1200 and predate A.D. 1890. Based on the lack of well-developed surface weathering (Table 1), the younger deposits in eastern Grand Canyon probably occurred in the later part of the interval A.D. 1200–1890.

DISCUSSION AND CONCLUSIONS

Late Holocene bouldery debris fans and sandy alluvial terraces of the Colorado River are the principal geomorphic features along the river in easternmost Grand Canyon. The terraces and fans are a locus of human activity for the past two to three millennia. Archaeologic sites are relatively abundant on these surfaces, consisting

mainly of long-abandoned camp sites and masonry structures. Debris fans are the more prominent geomorphic feature, as the terraces have substantially less topographic relief and are heavily reworked by wind. Debris fans range in size from about 10 000 to slightly more than 220 000 m²; median area of the debris fans is 53 730 m² ($N = 8$). The fans consist of an active channel entrenched into the broad surface of the fan, whose area is typically six times larger than the active channel. Fans of similar age, size, and morphology are present throughout Grand Canyon where the bedrock channel is wide enough for deposition and preservation of sediment.

Inactive fan surfaces have three topographically and temporally distinct segments that are identified and correlated in eastern Grand Canyon by relative topographic relief and degree of surface weathering. These surfaces are conformable with underlying debris-flow deposits, whose ages are contemporaneous with the ages of the surfaces. Topographically, the older surfaces are typically above younger surfaces. Weathering of younger fan surfaces is slight; they have little or no rock varnish on sandstone clasts, and limestone clasts are fresh with little surface roughness. Intermediate-age surfaces have weak stage-I carbonate morphology, rock varnish on 50%–100% of the clasts, and distinctly pitted limestone clasts, the result of prolonged exposure to acidified rainfall and biogenic activity. Older surfaces have stage-I carbonate morphology, somewhat

darker rock varnish on most clasts, and deeply pitted-limestone clasts.

The depth of weathering pits is used to distinguish between the intermediate-age and older-fan surfaces. Average depth and standard deviation (s) is 3.2 ($s = 0.8$) mm on the intermediate-age surfaces and 5.8 ($s = 1.7$) mm on the older surfaces ($N = 1156$ and 1301, respectively). An archaeological structure dated between A.D. 1000–1150 and constructed with limestone has average pit depth of 1.9 mm; this is an average deepening rate of 2.1 mm/1000 yr, using the median date of the structure. Therefore, most of the intermediate-age surfaces and all of the older surfaces are older than 1 ka, based on pit depth of limestone clasts.

Three alluvial terraces of the Colorado River are stratigraphically related to the debris-fan surfaces and deposits. These are referred to as the striped alluvium, named for distinctive, thin interbeds of reddish hill-slope sediment; the alluvium of Pueblo II age, which is characterized by abundant archaeological remains of the Kayenta Anasazi; and the alluvium of the upper mesquite terrace. The terraces were mapped on large-scale topographic maps and dated using radiocarbon methods and archaeological remains.

Stratigraphic information and 27 radiocarbon dates suggest the following late Holocene alluvial chronology of the Colorado River in eastern Grand Canyon: (1) deposition of the striped alluvium beginning before 770 B.C. and lasting until about A.D. 300; (2) erosion and nondeposition between about A.D. 300 and 700; (3) deposition of the alluvium of Pueblo II age at a lower position in the channel from about A.D. 700 to 1200; (4) another episode of downcutting and nondeposition from about A.D. 1200 to 1400; and (5) deposition of the upper mesquite terrace alluvium from about A.D. 1400 to 1880.

The causes of alternating fluvial deposition and erosion are not well understood in eastern Grand Canyon. Water in the Colorado River is derived from snowmelt in the headwaters of the Rocky Mountains, whereas the sediment load is mainly from tributaries of the Colorado Plateau (Andrews, 1991). Thus, climate of either region could influence alluviation in Grand Canyon in ways that are not immediately apparent. Nevertheless, the alluvial chronology of the Colorado River in eastern Grand Canyon correlates broadly with a late Holocene chronology of the southern Colorado Pla-

teau developed by Karlstrom (1988) and elaborated by Dean (1988, p. 129). The alluvium of Pueblo II age probably correlates with the upper Tsegi formation, and the upper mesquite terrace alluvium correlates roughly with the Naha formation, both of northeast Arizona and southern Utah (Hack, 1942; Cooley, 1962). Erosion in Grand Canyon around A.D. 1200–1400 correlates with widespread stream entrenchment on the southern Colorado Plateau at about this time.

Stratigraphic relations between the terraces and debris fans, radiocarbon dating of fine-grained distal facies of debris-flow deposits, and historic photographs were used to resolve the ages of debris-flow deposits. The older deposit dates from before about 770 B.C. until A.D. 660, although the maximum age is not well delimited. The intermediate-age deposit dates from after A.D. 660 until 1200, and the younger deposit dates from after A.D. 1200 until shortly before 1890. Most of the younger surfaces in eastern Grand Canyon are probably closer to the latter part of this interval, based on weakly developed surface weathering, historic photographs, and radiocarbon dates.

We think the maximum age of most older debris fans is probably late Holocene. An absolute age of 2.8 ka is indicated for the striped alluvium, based on the oldest of several radiometric dates from near the base of the alluvium. The alluvium is interbedded with a debris-flow deposit that elsewhere has surface-weathering characteristics similar to the older fan; thus we correlate the striped alluvium with the older debris-flow deposits. Furthermore, the position of the alluvium in the channel is related to the present elevation and course of the river. Deposits older than the striped alluvium are gravelly and occur in a bedrock channel of different alignment and higher elevation than the present channel.

Nevertheless, the maximum age of the striped alluvium and related debris-flow deposits is not well refined, as the basal contact of the alluvium is not exposed and is undated. Linear extrapolation of the 4 mm/1000 yr rate of maximum pit deepening suggests the oldest surfaces with pits up to 16 mm deep might be 4 ka. Likewise, extrapolation of the 2 mm/1000 yr rate of average pit deepening suggests the oldest surfaces with average depth of 10 mm might be 5 ka. These ages might be too old, depending on the relation between time and maximum and average pit depth. Early and middle Holocene debris fans and alluvium were not

found and are evidently not present, which probably results from nonpreservation or burial by younger deposits.

Because debris flows are instantaneous events, the deposits of a particular fan will probably not correlate exactly with the deposits of any other fan. Nevertheless, the three age categories are broadly defined periods of late Holocene debris-flow activity in eastern Grand Canyon. Too little is known presently about the correlation and specific dates of the fan-forming debris flows to offer more than speculation about their relation to late Holocene climate change. Moreover, late Holocene climate of the southern Colorado Plateau is poorly known, and the biseasonal precipitation pattern makes comparison with other regions difficult. Historic debris flows have occurred in summer from thunderstorms and in late fall from winter-frontal systems (Webb et al., 1989). If sediment supply was adequate, it seems likely that a long-term shift to frequent, intense rainfall in summer or late fall would increase debris-flow activity, thereby aggrading the fans.

Finally, conditions leading to deposition outside of the entrenched channel and aggradation of the fans do not occur often in eastern Grand Canyon. Indeed, deposition on the fan surfaces may have occurred only three times in 2800 yr. Although further work will be necessary to subdivide the three surfaces, it seems likely that the number of fan-forming debris flows on a particular fan is small.

If the entrenched configuration of the fans is typical, then aggradation of the fan surface requires the debris-flow channel to be overtopped, spreading sediment across the fan. This type of aggradation was reported in a different climate setting by Osterkamp et al. (1986), who studied late Holocene debris flows on the flanks of Mount Shasta in northern California. They recognized relatively small and frequent in-channel debris flows and large, relatively infrequent out-of-channel debris flows. In-channel debris flows correspond with the channelized debris-flow deposits of the present study. Out-of-channel flows are those of sufficient size to overtop a channel confinement, producing a mappable deposit on the fan surface; these correspond with the fan-forming debris flows.

Aggradation of segmented debris fans in eastern Grand Canyon probably results from changes of local base level and changes in frequency or magnitude of debris flow. The channel could be overtopped either by

an increase in the frequency of channelized-debris flows that eventually fill the channel, or by one or more relatively large debris flows that fill the channel and deposit sediment on the fan simultaneously. In either case, substantial, rapid deposition of tributary debris in the river channel would raise base level locally, reducing gradient of the debris-flow channel, causing it to aggrade. Entrenchment of the debris-flow channel probably results from lower base level following erosion of debris in the river channel. This causes local steepening of fan gradient and incision of a new debris-flow channel.

ACKNOWLEDGMENTS

This work was done in cooperation with the Bureau of Reclamation, Glen Canyon Environmental Studies. We thank program director David L. Wegner for continued support of the work and National Park Service archaeologist Janet R. Balsom for demonstrating the need for geoarchaeologic studies along the Colorado River in Grand Canyon. Robert H. Webb kindly provided the Stanton photographs as well as relocated photographs taken by Webb in 1990. Diana Elder-Anderson, Kirk C. Anderson, and Glenn R. Rink helped with trenching, measuring, sampling, and describing stratigraphic sections. Logistical support for five river trips to eastern Grand Canyon was provided by Brian Dierker, Chris Geanious, Doree Stonebreaker, and Greg Williams. Critical reviews and comments by Susan W. Kieffer, Theodore S. Melis, Waite R. Osterkamp, Marith C. Reheis, John C. Schmidt, and Robert H. Webb substantially improved an earlier version of the report.

REFERENCES CITED

- Altschul, J. H., and Fairley, H. C., 1989, Man, models, and management: An overview of the archaeology of the Arizona Strip and the management of its cultural resources: Report prepared for U.S. Department of Agriculture Forest Service and U.S. Department of Interior Bureau of Land Management Contract Number 53-8371-5-0054, 410 p.
- Andrews, E. D., 1991, Sediment transport in the Colorado River basin, *in* Colorado River ecology and dam management: Washington, D.C., National Academy of Science Press, p. 54–74.
- Blair, T. C., and McPherson, J. G., 1994, Alluvial fan processes and forms, *in* Abrahams, A. D., and Parsons, A. J., eds., *Geomorphology of desert environments*: New York, Chapman and Hall, p. 354–402.
- Bull, W. B., 1991, *Geomorphologic response to climatic change*: New York, Oxford University Press, 326 p.
- Carothers, S. W., and Brown, B. T., 1991, The Colorado River through Grand Canyon: Natural history and human change: Tucson, University of Arizona Press, 235 p.
- Cooke, R. U., Warren, A., and Goudie, A. S., 1993, *Desert geomorphology*: London, UCL Press, 526 p.
- Cooley, M. E., 1962, Late Pleistocene and recent erosion and alluviation in parts of the Colorado River system, Arizona and Utah: U.S. Geological Survey Professional Paper 450-B, p. B48–B50.
- Cooley, M. E., Aldridge, B. N., and Euler, R. C., 1977, Effects of the catastrophic flood of December 1966, North Rim area, eastern Grand Canyon, Arizona: U.S. Geological Survey Professional Paper 980, 43 p.

DEBRIS FANS AND ALLUVIAL CHRONOLOGY, GRAND CANYON

- Costa, J. E., 1984, Physical geomorphology of debris flows, *in* Costa, J. E., and Fleisher, P. J., eds., *Developments and applications of geomorphology*: Berlin, Springer-Verlag, p. 268-317.
- Danin, A., 1983, Weathering of limestone in Jerusalem by cyanobacteria: *Zeitschrift für Geomorphologie*, v. 27, p. 413-421.
- Danin, A., and Garty, J., 1983, Distribution of cyanobacteria and lichens on hillsides of the Negrev Highlands and their impact on biogenic weathering: *Zeitschrift für Geomorphologie*, v. 27, p. 423-444.
- Dean, J. S., 1988, Dendrochronology and paleoenvironmental reconstruction on the Colorado Plateau, *in* Gumerman, G. J., ed., *The Anasazi in a changing environment*: New York, Cambridge University Press, p. 119-167.
- Dolan, R., Howard, A., and Trimble, D., 1978, Structural control of the rapids and pools of the Colorado River in the Grand Canyon: *Science*, v. 202, p. 629-631.
- Euler, R. C., and Taylor, W. W., 1966, Additional archaeological data from Upper Grand Canyon: Nankowcap to Unkar revisited: *Plateau*, v. 39, p. 26-45.
- Fairley, H. C., Bungart, P. W., Coder, C. M., Huffman, J., Samples, T. L., and Balsom, J. R., 1994, The Grand Canyon river corridor survey project: Archaeological survey along the Colorado River between Glen Canyon Dam and Separation Canyon: Report prepared for Grand Canyon National Park Service, Cooperative Agreement No. 9AA-40-07920, 276 p.
- Graf, W. L., 1979, Rapids in canyon rivers: *Journal of Geology*, v. 87, p. 533-551.
- Hack, J. T., 1942, *The changing physical environment of the Hopi Indians of Arizona*: Cambridge, Massachusetts, Harvard University Press, *Papers of the Peabody Museum of American Archaeology*, v. 35, 12 pl., 54 figs., 85 p.
- Hamblin, W. K., and Rigby, J. K., 1968, Guidebook to the Colorado River, Part 1: Lee's Ferry to Phantom Ranch in Grand Canyon National Park: Provo, Utah, Brigham Young University Geology Studies, v. 15, part 5, 125 p.
- Hendricks, J. D., and Stevenson, G. M., 1990, Grand Canyon Supergroup: Unkar Group, *in* Bues, S. S., and Morales, M., eds., *Grand Canyon geology*: New York, Oxford University Press, p. 29-47.
- Hereford, R., 1993, Map showing surficial geology and geomorphology of the Palisades Creek archeologic area, Grand Canyon National Park, Arizona: U.S. Geological Survey Open-File Report 93-553, scale 1:2000, 1 pl., 21 p.
- Hereford, R., in press, Map showing surficial geology and geomorphology of the Palisades Creek area, Grand Canyon National Park, Arizona: U.S. Geological Survey Miscellaneous Investigations Series Map I-2499, scale 1:2000 (with discussion).
- Hereford, R., and Thompson, K. S., 1994a, Topographic map of the Nankowcap Rapids area, Marble Canyon, Arizona: U.S. Geological Survey Open-File Report 94-564, scale 1:2000.
- Hereford, R., and Thompson, K. S., 1994b, Topographic map of the Granite Park area, Grand Canyon, Arizona: U.S. Geological Survey Open-File Report 94-563, scale 1:2000.
- Hereford, R., Fairley, H. C., Thompson, K. S., and Balsom, J. R., 1993, Surficial geology, geomorphology, and erosion of archeologic sites along the Colorado River, eastern Grand Canyon, Grand Canyon National Park, Arizona: U.S. Geological Survey Open-File Report 93-517, 45 p., 4 pl.
- Hooke, R. LeB., 1987, Mass movement in semi-arid environments and the morphology of alluvial fans, *in* Anderson, M. G., and Richards, K. S., eds., *Slope stability*: New York, John Wiley and Sons, p. 505-529.
- Howard, A., and Dolan, R., 1981, Geomorphology of the Colorado River in the Grand Canyon: *Journal of Geology*, v. 89, p. 259-298.
- Huntoon, P. W., Billingsley, G. H., Breed, W. J., Sears, J. W., Ford, T. D., Clark, M. D., Babcock, R. S., and Brown, E. H., 1986, Geological map of the eastern part of Grand Canyon National Park, Arizona: Grand Canyon, Arizona, Grand Canyon Natural History Association, scale 1:62 500.
- Jones, A. T., 1985, A cross section of Grand Canyon archeology: Excavations at five sites along the Colorado River: Tucson, Arizona, National Park Service Publications in Anthropology Number 28, 357 p.
- Karlstrom, T. N. V., 1988, Alluvial chronology and hydrologic change of Black Mesa and nearby regions, *in* Gumerman, G. J., ed., *The Anasazi in a changing environment*: New York, Cambridge University Press, p. 45-91.
- Kieffer, S. W., 1985, The 1983 hydraulic jump in Crystal Rapid: Implications for river running and geomorphic evolution in the Grand Canyon: *Journal of Geology*, v. 93, p. 385-405.
- Kieffer, S. W., 1988, Hydraulic map of Crystal Rapids, Grand Canyon, Arizona: U.S. Geological Survey Miscellaneous Investigation Series I-1897-H, scale 1:1000.
- Kieffer, S. W., 1990, Hydraulics and geomorphology of the Colorado River in the Grand Canyon, *in* Bues, S. S., and Morales, M., eds., *Grand Canyon geology*: New York, Oxford University Press, p. 333-383.
- Klein, J., Lerman, J. C., Damon, P. E., and Ralph, E. K., 1982, Calibration of radiocarbon dates: *Radiocarbon*, v. 24, p. 103-150.
- Klein, M., 1984, Weathering rates of tombstones measured in Haifa, Israel: *Zeitschrift für Geomorphologie*, v. 28, p. 105-111.
- Lucchitta, L., 1991, Topographic maps of the Palisades-Unkar area, Grand Canyon, Arizona: U.S. Geological Survey Open-File Report 91-535, scale 1:5000.
- Machette, M. N., and Rosholt, J. N., 1991, Quaternary geology of the Grand Canyon, *in* Morrison, R. B., ed., *Quaternary nonglacial geology of the conterminous United States*: Boulder, Colorado, Geological Society of America, *Geology of North America*, v. K-2, p. 397-401.
- McFadden, L. D., Ritter, J. B., and Wells, S. G., 1989, Use of multiparameter relative-age estimation and correlation of alluvial fan surfaces on a desert piedmont, eastern Mojave Desert, California: *Quaternary Research*, v. 32, p. 276-290.
- Melis, T. S., and Webb, R. H., 1993, Debris flows in Grand Canyon National Park, Arizona: Magnitude, frequency, and effects on the Colorado River, *in* Shen, H. W., Su, S. T., and Wen Feng, eds., *Hydraulic engineering '93*, Proceedings of the 1993 conference: Hydraulics Division, American Society of Civil Engineers, v. 2, p. 1290-1295.
- Melis, T. S., Webb, R. H., and Wise, T. W., 1993, Effect of historic debris flows on the Colorado River in Grand Canyon: *Geological Society of America Abstracts with Programs*, v. 25, no. 6, p. A-142.
- Melis, T. S., Webb, R. H., Griffiths, P. G., and Wise, T. J., 1994, Magnitude and frequency data for historic debris flows in Grand Canyon National Park and vicinity: U.S. Geological Survey Water Resources Investigations Report 94-4214, 290 p.
- O'Connor, J. E., Ely, L. L., Wohl, E. E., Stevens, L. E., Melis, T. S., Kale, V. S., and Baker, V. R., 1994, A 4500-year record of large floods on the Colorado River in the Grand Canyon, Arizona: *Journal of Geology*, v. 102, p. 1-9.
- Osterkamp, W. R., Hupp, C. R., and Blodgett, J. C., 1986, Magnitude and frequency of debris flows, and areas of hazard on Mount Shasta, northern California: U.S. Geological Survey Professional Paper 1396-C, p. C1-C21.
- Potochnik, A. R., and Reynolds, S. J., 1990, Side canyons of the Colorado River, Grand Canyon, *in* Bues, S. S., and Morales, M., eds., *Grand Canyon geology*: New York, Oxford University Press, p. 461-481.
- Reheis, M. C., Sawyer, T. L., Slate, J. L., and Gillespie, A. R., 1993, Geologic map of the late Cenozoic deposits and faults in the southern part of the Davis Mountain 15' quadrangle, Esmeralda County, Nevada: U.S. Geological Survey Miscellaneous Investigation Series I-2342, scale 1:62 500.
- Schmidt, J. C., 1990, Recirculating flow and sedimentation in the Colorado River in Grand Canyon, Arizona: *Journal of Geology*, v. 98, p. 709-724.
- Schmidt, J. C., and Graf, J. B., 1990, Aggradation and degradation of alluvial sand deposits, 1965 to 1985, Colorado River, Grand Canyon National Park, Arizona: U.S. Geological Survey Professional Paper 1493, 74 p.
- Sellers, W. D., and Hill, R. H., 1974, Arizona climate 1931-1972: Tucson, University of Arizona Press, 616 p.
- Smith, B. J., 1988, Weathering of superficial limestone debris in a hot desert environment: *Geomorphology*, v. 1, p. 355-367.
- Smith, B. J., 1994, Weathering processes and forms, *in* Abrahams, A. D., and Parsons, A. J., eds., *Geomorphology of desert environments*: New York, Chapman and Hall, p. 39-53.
- Smith, D. L., and Crampton, C. G., 1987, The Colorado River survey: Salt Lake City, Utah, Howe Brothers, 305 p.
- Stevens, L., 1990, *The Colorado River in Grand Canyon, A guide*: Flagstaff, Arizona, Red Lake Books, 110 p.
- Taylor, R. E., 1987, *Radiocarbon dating*: New York, Academic Press, 212 p.
- Webb, R. H., Pringle, P. T., Reneau, S. L., and Rink, G. R., 1988, Monument Creek debris flow, 1984: Implications for formation of rapids on the Colorado River in Grand Canyon National Park: *Geology*, v. 15, p. 50-54.
- Webb, R. H., Pringle, P. T., and Rink, G. R., 1989, Debris flows from tributaries of the Colorado River, Grand Canyon National Park, Arizona: U.S. Geological Survey Professional Paper 1492, 39 p.
- Wells, S. G., McFadden, L. D., and Dohrenwend, J. C., 1987, Influence of late Quaternary climatic changes on geomorphic and pedogenic processes on a desert piedmont, eastern Mojave Desert, California: *Quaternary Research*, v. 27, p. 130-146.
- Williams, G. P., and Wolman, M. G., 1984, Downstream effects of dams on alluvial rivers: U.S. Geological Survey Professional Paper 1286, 83 p.

MANUSCRIPT RECEIVED BY THE SOCIETY FEBRUARY 21, 1995
 REVISED MANUSCRIPT RECEIVED JULY 3, 1995
 MANUSCRIPT ACCEPTED JULY 14, 1995